

County of El Paso Purchasing Department 800 E. Overland Room 300 El Paso, Texas 79901

(915) 546-2048 / Fax: (915) 546-8180

www.epcounty.com

ADDENDA 2

To: All Interested Vendors

From: Blanca Güereca, Procurement Data Analyst

Date: February 14, 2020

Subject: Bid 20-016 Ascarate Park Lift Station and Sanitary Sewer Improvements

The Purchasing Department has received the following questions:

1. Is this a design or construction project? For what phase is this solicitation?

RESPONSE: This is a bid request for the construction of the Ascarate park lift station and sanitary sewer improvements and should be built as per plans.

2. Is there a plan holders or bidders list available and how can the vendors confirm that the bid date and time are unchanged?

RESPONSE: Information regarding this and any other bid can be found on the County's website: www.epcounty.com Select: Directory, Purchasing, List of Bids.

3. Drawing C-7 shows new lift station along with Spec Section 02530 Grinder Pump Unit. Is there information on the plans showing power source & electrical requirements for the lift station?

RESPONSE: Sanitary Sewer Detailed View, on sheet C-3, indicates that electrical power should be extended from existing meter located adjacent to existing abandoned lift station. Existing power available is 230v/60hz/1 phase. Proposed lift station power requirements are 120/240v, 60 hz, 1 phase.

4. Is there a cost estimate or budget released for this project and is there estimated start/end dates for this project?

RESPONSE: There is no cost estimate at this time. The project shall be started as soon as it is approved and awarded by the Court.

The following is a recap of the pre-bid conference held on Thursday, February 13, 2020:

1. Will there be a Geotech test done by the owner or the contractor?

RESPONSE: The density test will be done by the owner.

2. Are the facilities currently functional?

RESPONSE: No, they are completely shut down.

3. Is the sanitation contract not going to take place?

RESPONSE: Once the project is complete, sanitation will continue.