



County of El Paso Purchasing Department  
800 E. Overland Room 300  
El Paso, Texas 79901  
(915) 546-2048 / Fax: (915) 546-8180

---

## **ADDENDUM 2**

**To:** All Interested Bidders  
**From:** Lucy Balderama, Inventory Bid Technician  
**Date:** November 29, 2011  
**Subject:** BID # 11-049, Ascarate Park Entrance Renovation

---

- **Due to holiday, Deadline for questions is extended for Friday, December 2, 2011 at 12:00 noon.**

---

### **ADDENDUM NO. 2**

ISSUED: 25 November, 2011

**ASCARATE PARK ENTRANCE  
RENOVATIONS ASCARATE  
PARK RENOVATION  
PROJECT EL PASO, TEXAS  
SITES SOUTHWEST PROJECT NO. 2010047**

---

This Addendum forms as part of the Contract Documents and modifies the original specifications and drawings dated November 8, 2011. Acknowledge receipt of this addendum in the space provided in the Bid Form. Failure to do so will subject the bidder to disqualification.

**BID DATE AND TIME IS UNCHANGED BY THIS ADDENDUM AND REMAINS AS IS.**

### **ELECTRICAL SPECIFICATIONS**

There have been no modifications made to the electrical specifications at this time.

### **ELECTRICAL PLANS**

## **SHEET E-102:**

- ITEM NO. 1 Keyed Note 7 shall read, "As part of base bid work in this area, contractor shall provide area lighting type "B" and circuitry shown to and from each pole. If subtractive alternate #5 is awarded, contractor shall provide heavy duty, traffic rated in-ground pull box at locations shown for lighting type "B". Area lighting type "B" will not be provided if subtractive alternate is accepted. Regardless if subtractive alternate is accepted, conduit and wire system shown will be provided through out. Saw-cut asphalt to install conduit system shown in round-about. Patch and repair as per pre-construction conditions. Refer to drawings for more information."
- ITEM NO. 2 As part of base bid work on this sheet, contractor shall provide and install 3/4" PVC sch. 40 conduit system underground to each rock sign structure shown and noted on sheets LC-101 and LC-102. If possible and/or in close proximity, contractor may connect conduit system to new lighting shown on plans. Regardless, all conduit systems mentioned above shall be routed back to the ticket booth and stubbed below the interior panel for future sign lighting connection if not connected to new lighting. Provide pull-string for each conduit system. Include saw-cut, patch, and repair of asphalt and landscape where required. Coordinate with landscape contractor prior to any work.

---

**The Purchasing Department received questions relating to the above referenced Bid during the pre-bid conference; the following is the response to the questions:**

**1. Will this be a Best value or Low bid?**

It will be a low bid.

**2. Should we state that in our bid?**

The problem with value engineering is that if it is a part of the bid process then you are value engineering for everybody. It is a matter of your response to the bid. It would be like suggesting an alternate at the time of the bid.

**3. Are there Parking meters that we need to buy?**

No.

**4. Is there any tap fees or water fees?**

All water fees will be paid by the County.

**5. When will electrical be done?**

It is up to the contractors.

**For a site visit of the area call Reynaldo Chavez at 772-5605**